

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of work: Detailed Estimate for the Work of Improvements to Roads and Drains at Anam Enclave in Ward No.06 Byatarayanapura Sub Division

		Estimate Cost Rs.						2000000.00	
SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1, P. No. 5/ Item No. 2.1/ PWD SR 2014-15	cum							
	Desilting of Drains								
	3rd main Road		2	400.00	0.35	0.25	70.00		
	2nd Main Cross Road		2	66.00	0.35	0.25	11.55		
	Burn Cutting								
	3rd main Road		2	400.00	1.20	0.25	240.00		
	2nd Main Cross Road		2	66.00	1.20	0.25	39.60		
							361.15	146.88	53046.00
	Basic Rate	136.00							
	Area Weightage @ 8%	10.88							
	Total	146.88							
2	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum							
	For Culverts		2	6.50	1.95	1.05	26.62		
							26.62	264.60	7043.00
	Basic Rate	245.00							
	Area Weightage @ 8%	19.60							
	Total	264.60							
3	Removing B.S Slab of Drain and stacking Page No. 25/ Item No. 5.32/ PWD SR 2014-15	Sqm							
			2	400.00	1.65		1320.00		
			2	66.00	1.65		217.80		
							1537.80		
	Deduct 20% Missing Slabs						307.56		
							1230.24	58.32	71748.00
	Basic Rate	54.00							

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	Area Weightage @ 8%	4.32							
	Total	58.32							
4	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 25/ Item No. 5.33/ PWD SR 2014-15	Sqm							
							Qty Vide Item No.3	1230.24	
							1230.24	75.60	93006.00
	Basic Rate	70.00							
	Area Weightage @ 8%	5.60							
	Total	75.60							
5	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2014-15	Sqm							
	For Missing slabs (20%)						Missing Slabs	307.56	
							307.56	639.36	196642.00
	Basic Rate	592.00							
	Area Weightage @ 8%	47.36							
	Total	639.36							
6	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2, No. 12/ Item No. 4.3/ PWD SR 2014-15	Cum							
	For Culverts		2	6.50	1.95	0.15	3.80		
							3.80	4847.04	18431.00
	Basic Rate	4488.00							
	Area Weightage @ 8%	359.04							
	Total	4847.04							
7	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2014-15	cum							
	For Culverts		2X2	6.50	0.60	0.45	7.02		
							7.02	3836.16	26930.00
	Basic Rate	3552.00							
	Area Weightage @ 8%	284.16							
	Total	3836.16							

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
8	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2014-15	Sqm							
	For Culverts		2X2	6.50	0.50	0.45	5.85		
							5.85	4542.48	26574.00
	Basic Rate	4206.00							
	Area Weightage @ 8%	336.48							
	Total	4542.48							
9	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.34/ PWD SR 2014-15	Sqm							
	For Culverts		2	6.50	0.60		7.80		
	For Sides		2X2	6.50	0.23		11.96		
			2X2	1.65	0.23		3.04		
							22.80	260.28	5933.00
	Basic Rate	241.00							
	Area Weightage @ 8%	19.28							
	Total	260.28							
10	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2014-15	cum							
	For Culverts		2X2	6.50	0.50	0.10	1.30		
	Vent Bed		2	6.50	0.60	0.10	0.78		
							2.08	5287.68	10998.00
	Basic Rate	4896.00							
	Area Weightage @ 8%	391.68							
	Total	5287.68							
11	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2014-15	Sqm							
	For Culverts		2X2	6.50		0.50	13.00		
							13.00	91.80	1193.00
	Basic Rate	85.00							

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	Area Weightage @ 8%	6.80							
	Total	91.80							
12	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2014-15	Cum							
	For Culverts		2	6.50	1.65	0.23	4.93		
							4.93	6065.28	29923.00
	Basic Rate	5616.00							
	Area Weightage @ 8%	449.28							
	Total	6065.28							
13	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2014-15	Tone							
	0.080 Ton/Cum		0.090	4.93			0.44	78351.84	34789.00
	Basic Rate	72548.00							
	Area Weightage @ 8%	5803.84							
	Total	78351.84							
14	KSRRB M400-17: Providing, - laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406, No. 154/ Item No. 20.18/ PWD SR 2014-15	Cum							

[illegible]

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	Total	67.32							
							Grand Total		1976253.00
18	For 1% Third Party Inspection Charges								19763.00
19	Miscellaneous Charges	L/S							3984.00
							Total		2000000.00

Rupees Twenty Lakh(s) Only

CERTIFICATE

- 1 The work spot has been inspected and the work is found necessary.
- 2 This estimate is prepared as per PWD SR of 2014-15
- 3 The provisions were made in this estimate are necessary and adequate.
- 4 This works come under B.B.M.P. limits.


 Assistant Engineer
 ಬಿ.ಬಿ.ಎಂ.ಪಿ. ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ
 Executive Engineer
 Byatarayanapura Division
 Bruhat Bangalore Mahanagara Palike


 Assistant Executive Engineer
 Assistant Executive Engineer
 Byatarayanapura Sub Division
 B.B.M.P. Bangalore

ADMINISTRATIVELY SANCTIONED FOR Rs. 20...

Rupees Twenty Lakhs only

Under _____

Registered as EE () No. _____ 3...9....

Subject to conditions contained in

enclosed memo EE () No. _____ 101....

Dt. Adel Commr Estimate AS 1159/14-15

No. _____
dated _____ Rs. 20, lakhs



 Asst Commissioner
 (Yelahanka Zone)
 BBMP, Bengaluru-92

20.00 Lakh
Rs. Twenty Lakhs only
94
TS/EE/94/14-15
29/10/14


Name of Work: Improvements to Roads and Drains at Anam Enclave in Ward No.06
Byatarayanapura Sub Division

(5)

Est cost Rs - 20.00 Lakhs



L-66mtr W-5.0mtr

2nd cross

3rd cross

L-40mtr
W-5.0mtr

ANAM ENCLAVE

HITENTION ROAD

INDEX

 PROPOSED ASPHALT WORK


ಸಹಾಯಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ


Assistant Executive Engineer
Byatarayanapura Sub Division
B.B.M.P. Bangalore

← THANISANDRA MAIN ROAD → NAGAWARA